



West Bengal Minorities' Development & Finance Corporation

(A Statutory Corporation of Govt. of West Bengal)

No : 603 -MDC/OB-06

Date: 14.02.2020

NOTICE INVITING QUOTATION

NIQ NO:- AMBER-FVB -1 of 2020-21

Sealed quotations are invited from the willing resourceful agencies having experience in Fire fighting works as per particulars given below:-

- i). Name of Work : Ventilation work for Basement of WBMDFC at AMBER Building Salt Lake Kolkata-64.
- ii). Time of Completion : 15(fifteen) days from the date of issue of work order.
- iii). Eligibility of Contractor : Bonafide and resourceful manufacturers, firms agencies having experience credentials for such type of work.
- iv). Earnest money : Rs.9900.00 in favour of WBMDFC through NEFT/RTGS (Beneficiaries Bank Name- SBI, SaltLake, Kolkata IFS Code No. SBIN0001612, Bank A/cNo. 35632345165.
- v). Last date of submission of Quotation : 27.02.2020 up to 2. P.M
- vi). Opening date of quotation : 27.02.2020 at 4 P.M

The willing agencies will have to quote their rate in their letter pad in accordance with the attached blank work schedule. Expiry date to be minimum one (01) year from the date of refilling.

Rates are to be quoted both in words and in figures inclusive of GST and all taxes & other incidental charges viz carriage charge, fixing charges etc.

One number of each category of Fire extinguishers will have to be tested by the selected agency at his own cost of the agencies. Necessary certification will have to be given by the selected agency for each refilled extinguishers.

Conditional Rates will not be accepted.

All corrections are to be initialled.

Willing agencies will have to produce the copies of valid up to date professional tax clearance certificate, Trade license, of PAN Card, GST Registration certificate and credential along with their quotation papers.

The work is to be carried out as per direction of Corporation.

All agencies are requested to be present at the time of opening of sealed quotation.

Managing Director, WBMDFC reserves the right to reject any quotation or all quotations without assigning any reason.


Managing Director

Encl:- Blank work schedule

No : 603 -MDC/OB-06

Date: 14.02.2020

Copy forwarded for information & wide circulation to the:

- 1) PA to Spl. Secretary, MA & ME Department, Govt. of WB
- 2) PA to Joint Secretary, Fire Department, Govt. of WB
- 3) Chief Engineer (South Zone), PWD, NS Building, Kolkata-1
- 4) General Manager (Admn) WBMDFC
- 5) Chief Accounts Officer, WBMDFC
- 6) Office Notice Board
- 7) Department Website


Managing Director

**WORK SCHEDULE FOR BASEMENT VENTILATION WORK OF THE AMBER BUILDING OF WEST BENGAL MINORITIES'
DEVELOPMENT & FINANCE CORPORATION AT SALT LAKE, DURING THE YEAR 2019-20**

Sl No.	Item Description	CFM	Sp	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	Supply, installation testing & commissioning of Axial fan ,Each fan shall be complete with mounting legs, outlet screen, flexible connection at inlet or outlet and Class-H Motor suitable for 415+10% volts, 50 cycles , 3 phase AC supply. (Motor speed shall 1450 rpm). The fan with 2 hours rating at 300 drg C of high temperature. The Fans are Sound and Air Performance approved (LOW NOISE) Fan Approve make: Greenheck (RA-560 series)						
1.a	SMOKE EXTRACTION FAN (Basement Ventilation Area)	6500	20mm	2.00	Nos.		0.00
1.b	Cable size- 3core-4.0 sqmm Al. Armoured Cable.			60.00	Rmt.		0.00
2	Supply, fitting and fixing of Central Monitor all complete as per specification & direction of Engineer-in-Charge.			10.00	Nos.		0.00
3	Supply, fitting and fixing of Relay Switch as per specification & direction of Engineer-in-Charge.			10.00	Nos.		0.00
4	Supply, fitting and fixing of SMPS as per specification & direction of Engineer-in-Charge.			10.00	Nos.		0.00
5	Electrical Stater panel with starters for all EXHAUST AXIAL FANS, located in Auditorium Area Manual Stater panel			1.00	Lot		0.00
6	Supply, fitting and fixing of Air Exhaust duct at Pump House Roof including cutting of RCC Roof, fixing of Exhaust duct, Exhaust Fan all complete as per specification & direction of Engineer-in-Charge.			1.00	Lot		0.00
7	Core cutting, Duct making for basement ventilation for all complete as per drawing and direction of Engineer-in-Charge			1.00	Lot		0.00
8	Installation, Testing and Commissioning Charges for all equipments.			1.00	Lot		0.00
9	Cable size 1.5 sqmm x 2 core Copper Cable with 20 mm PVC Conduit all complete specification & direction of Engineer-in-Charge.			100.00	Rmt.		0.00
						Total	0.00

[Handwritten Signature]
14/2/2020

[Handwritten Signature]

[Handwritten Signature]